

Annexure-A

1	Fixing of Junction box of size 12' x 10' x4' made of CRC 1.6 mm sheet paint/powder coated with provision of cable connection with 4 No Al. Bus bar of Size 25mmx6mm mounted on epoxy insulator , with 40 mm hole 2 No fitted with insulation Glands for Multicore Cable. Along with MS Clamp to be mounted on pole. (Junction box will be supplied by SMVDU)	No	20		
2	Fixing of 11 KV 10KN Pin Insulator (Polymer Type) as required .(Pin insulator will be supplied by SMVDU)	No	120		
3	Fixing 11 KV 45 KN Disc Insulator (Polymer Type) with fitting .(Disc insulator will be supplied by SMVDU)	Set	60		
4	Fixing of MS Channel Cross Arm 75x40 of 7feet length as required .(MS channel cross arm will be supplied by SMVDU)	No	20		
5	Fixing of MS Channel Cross Arm 75x40 of 9 feet length as required. .(MS channel cross arm will be supplied by SMVDU)	No	12		
6	Fixing of MS Channel Cross Arm 75x40 of 5 feet length as required.(MS Channel Cross arm will be supplied by SMVDU)	No	40		
7	Erectioning of GO Set 11 KV (Polymer Type) with GI pipe of dia 25mm of 6mtr length med type. Complete as required complete(GO set will be supplied by SMVDU)	Set	4		
8	Erectioning of DO Set 11 KV (Polymer Type) (DO set will be supplied by SMVDU)	Set	4		
9	Fixing of MS Angle 40x40x6mm Wherever required. (MS angle will be supplied by SMVDU)	kg	100		
10	Erection of Lightening Arrestor station type , Polymer make , Class II , 9 KV , Gapless Metal Oxide Type .(LA set will be supplied by SMVDU)	No	2		
11	Laying of 3.5 core X150 sqmm steel armoured 1.1 kv grade aluminium conductor LT cable. (LT cable will be supplied by SMVDU)	mtr	50		

6