

**Annexure-A**

S.no	Description/Particular	Unit	Qty	Rate in Rs.	Amount in Rs.
1	Fixing of Junction box of size 12' x 10' x 4' made of CRC 1.6 mm sheet paint/powder coated with provision of cable connection with 4 No Al. Bus bar of Size 25mmx6mm mounted on epoxy insulator, with 40 mm hole 2 No fitted with insulation Glands for Multicore Cable. Along with MS Clamp to be mounted on pole. ( Junction box will be supplied by SMVDU)	No	20		
2	Fixing of 11 KV 10KN Pin Insulator ( Polymer Type ) as required .( Pin insulator will be supplied by SMVDU)	No	120		
3	Fixing 11 KV 45 KN Disc Insulator ( Polymer Type ) with fitting .( Disc insulator will be supplied by SMVDU)	Set	60		
4	Fixing of MS Channel Cross Arm 75 X 40 of 7 feet length as required .( MS channel cross arm will be supplied by SMVDU)	No	20		
5	Fixing of MS Channel Cross Arm 75 X 40 of 9 feet length as required. .( MS channel cross arm will be supplied by SMVDU)	No	12		
6	Fixing of MS Channel Cross Arm 75 X 40 of 5 feet length as required.( MS Channel Cross arm will be supplied by SMVDU)	No	40		
7	Erectioning of GO Set 11 KV (Polymer Type) with GI pipe of dia 25mm of 6mtr length med type. Complete as required complete( GO set will be supplied by SMVDU)	Set	4		
8	Erectioning of DO Set 11 KV ( Polymer Type ) ( DO set will be supplied by SMVDU)	Set	4		
9	Fixing of MS Angle 40x 40x 6mm Wherever required. ( MS angle will be supplied by SMVDU)	kg	100		
10	Erection of Lightning Arrestor station type , Polymer make , Class II , 9 KV , Gapless Metal Oxide Type .( LA set will be supplied by SMVDU)	No	2		
11	Laying of 3.5 core X150 sqmm steel armoured 1.1 kv grade aluminium conductor LT cable. ( LT cable will be supplied by SMVDU)	mtr	50		

10  
/

no: SMVDU/Engg / 18/744-48  
dt: 21-06-2018